## CHITALDRUG DIVISION.

*Dated 2nd February* 1918.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 5th March 1918, for constructing a Police Station and lines for 1 daffedar and 4 men at Sanikere, Challakere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promisory Notes as earnest money, and be superscribed "Tender for constructing a Police Station and lines for 1 daffader and 4 men at Sanikere, Challakere Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing Police Station and lines for 1 Daffedar and 4 constables at Sanikere, Challakere Taluk.

| No. | Items of work | Per | Total Quantity |
|---|---|---|---|
| 1 | Earthwork excavation gravelly soil for foundation and filling in basement including watering and tamping. | C. yd. | 143 |
| 2 | Burnt stone in clay foundation and basement ... ... ... | C. ft. | 5,484 |
| 3 | Burnt brick in clay superstructure ... ... ... ... | " | 4,369 |
| 4 | Burnt brick in mortar superstructure and door jamps, etc. ... ... | " | 1,186 |
| 5 | Burnt brick in chunam coping with plastering ... ... ... | R. ft. | 253 |
| 6 | Burnt stone slabs dressed 6" thick ... ... ... ... | S. ft. | 718 |
| 7 | Teakwood lock-up doors as per plan with iron bars, etc, complete ... ... | " | 49 |
| 8 | Honneywood battened door with iron claps, etc., complete ... ... | " | 523 |
| 9 | Honneywood windows battened with iron bars and clamps, etc., complete ... | " | 60 |
| 10 | Honneywood ventilators with iron bars expanded metal, etc., complete ... | " | 31 |
| 11 | Honneywood work wrought and put up complete ... ... ... | C. ft. | 147·00 |
| 12 | Roofing with 1st class Mangalore tiles on teak reepers, etc., complete ... | Sq. | 32·38 |
| 13 | Ridge tiles set in mortar and cement pointing ... ... ... | R. ft. | 98 |
| 14 | Chunam borders over roof ... ... ... ... | " | 109 |
| 15 | Teakwood ceiling below rafters, reepers for lock-up rooms, complete... ... | S. ft. | 210 |
| 16 | Chunam plastering ... ... ... ... ... | Sq. | 125·6 |
| 17 | White and colourwashing 2 coats ... ... ... | " | 125·86 |
| 18 | Honneywood eave board 9" wide 1" thick ... ... ... | R. ft. | 437 |
| 19 | Wood oiling wood work 2 coats ... ... ... ... | Sq. | 14·29 |
| 20 | Tarring wood work 2 coats ... ... ... ... | " | 15·50 |
| 21 | Teakwood railings as per plan ... ... ... ... | R. ft. | 52 |
| 22 | Flooring with 1st Class Mangalore tiles over 3" concrete bed and cement pointing ... | Sq. | 11·67 |
| 23 | Flooring with Caddappa slabs over 3" concrete bed and cement pointing ... | " | 5·77 |
| 24 | Teakwood gate with iron works, etc.. complete ... ... ... | S. ft. | 16 |
| 25 | Silicate painting 2 coats ... ... ... ... | Sqr. | 18·15 |
| 26 | Constructing "V" shaped drains and bad water including cement pointing, etc. | R. ft. | 304 |
| 27 | Flooring with gravel including watering and taping ... ... ... | C. yd. | 18 |
| 28 | Teakwood finials as per plan ... ... ... ... | Each | 4 |
| 29 | Teakwood pendants do ... ... ... | " | 8 |
| 30 | Cutting grooves and dressing stone pillars ... ... ... | " | 2 |
| 31 | Constructing seats and drain pipe ... ... ... ... | " | 5 |
| 32 | Clearing site and levelling ground ... ... ... ... | Lump sum | Rs. |
| 33 | Providing chimney over kitchen for smoke escape ... ... | Each | 5 |
| 34 | Providing ½" diameter galvanised iron pipe to drain water from latrine and kitchen | " | 10 |
| 35 | Constructing cisteren in kitchen with burnt stone slabs and cement pointing including plastering to sides, etc. | " | 5 |
| 36 | Providing pestle and mortar stones ... ... ... ... | " | 5 |

*Dated 2nd Februafy* 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 5th March 1918, for

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed, "Tender for constructing quarters for one Jamedar and lines for men at Bharmasagara, Chitaldrug Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Northern Circle, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing quarters for one Jamedar and lines for one Daffedar and 6 men at Bharmasagara, Chitaldrug Taluk.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Earthwork excavation foundation in gravelly soil and filling in basement including watering and tamping. | C. yd. | 216 |
| 2 | Burnt stone in clay foundation and basement ... ... ... | C. ft. | 6,999 |
| 3 | Burnt brick in clay superstructure ... ... ... | " | 5,229 |
| 4 | Burnt brick in mortar tops of walls and doors and windows, jambs, etc. | " | 1,404 |
| 5 | Archwork burnt brick in mortar ... ... ... | " | 20 |
| 6 | Coping with burnt brick in mortar over compound wall including plastering, etc., complete. | R. ft. | 312 |
| 7 | Burnt stone slabs 6" thick dressed ... ... ... ... | S. ft. | 914 |
| 8 | Chunam pointing to basements ... ... ... ... | Sqr. | 5·55 |
| 9 | Chunam plastering ... ... ... ... | " | 131·59 |
| 10 | White and colour washing ... ... ... ... | " | 131·59 |
| 11 | Honneywood work wrought and put up ... ... ... | C. ft. | 182·49 |
| 12 | Teakwood battened doors with iron clamps, hinges, etc., complete ... | S. ft. | 754 |
| 13 | Teakwood battened windows with iron bars, locks and hinges, etc., complete ... | " | 103 |
| 14 | Teakwood battened ventilator, iron bar, etc., complete ... ... ... | " | 39 |
| 15 | Teakwood shelf with shutters including planks, hinges, etc, complete ... | " | 12 |
| 16 | Roofing with 1st class Mangalore tiles over teak reepers, etc., complete ... | Sqr. | 39·08 |
| 17 | Ridge tiles set in mortar ... ... ... ... | R. ft. | 139 |
| 18 | Cuddappah slabs flooring over 3" concrete bed and cement pointing ... | Sqr. | 7·56 |
| 19 | Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing etc., complete. | " | 11·97 |
| 20 | Zinc sheeting to valley ... ... ... ... | S. ft. | 30 |
| 21 | Teakwood planking below valley 1" thick ... ... ... | " | 20 |
| 22 | Chunam patties to valley with cement plastering, complete ... ... | R. ft. | 10 |
| 23 | Binding wall over roof as per detail estimate ... ... ... | " | 91 |
| 24 | Cornice 9" thick ... ... ... ... ... | " | 129 |
| 25 | Teakwood finials ... ... ... ... ... | Each | 4 |
| 26 | Wood oiling to wood work two coats ... ... ... ... | Sqr. | 18·48 |
| 27 | Silicate painting to doors and windows and ventilators two coats ... | " | 23·79 |
| 28 | Providing sinks 2'×2' including burnt stone flooring and cement pointing ... | Each | 2 Nos. |
| 29 | Providing hearth in bath and kitchen ... ... ... ... | " | 2 |
| 30 | Providing 1½" diameter galvanized iron pipe to drain off water ... ... | " | 16 |
| 31 | Constructing V-shaped drain burnt stone slabs and cement pointing ... | R. ft. | 240 |
| 32 | Constructing masonry chimney as per plan in brick in mortar including plastering. | Each | 1 No. |
| 33 | Gravel flooring including lead ... ... ... ... | C. yd. | 20 |
| 34 | Honneywood eave board 9"×1" ... ... ... ... | R. ft. | 414 |
| 35 | Providing seats in latrine burnt brick in mortar and cement plastering ... | L. S. | |
| 36 | Tarring two coats walls of latrine and wood work imbedded in walls ... | " | |
| 37 | Clearing, site levelling ground and forming road, etc. ... ... ... | " | |
| 38 | Providing chimney over kitchen ... ... ... ... | Each | 7 |
| 39 | Teakwood pendants ... ... ... ... ... ... | " | 4 |
| 40 | Constructing cistern in kitchen 2'×2' ... ... ... ... | " | 2 |
| 41 | Providing pestle and mortar stones for each unit ... ... ... | " | 8 |

N. ANANDALWAR,
*Executive Engineer.*

## MISCELLANEOUS DEPARTMENTS.

### GENERAL AND REVENUE SECRETARIAT.

No. G. 9629—*G. M.* 14-17-8, *dated* 16*th January* 1918.

Notice is hereby given that sealed tenders will be received by the Registrar, General and Revenue Secretariat, up to Saturday the 9th February 1918, for the supply of longcloth, mull, etc., as shown below:—

2. The quantity of each kind required is only approximately noted and is not guaranteed.

3. Tenders should be written on paper of foolscap size and should be accompanied by a statement showing the rates at which the different items can be supplied at the General and Revenue Secretariat.